Project Location



Environmental Mitigation Measures

Operation Phase

- > Air emission from stack :
- Monitoring TSP, SO₂, NO_X emission from stacks
- Controlling emission from the stacks, and installing the Continuous Emission Monitoring System (CEMs)
- ➤ **ambient air quality**: Monitoring TSP, PM10, SO₂, NO₂ and Wind speed in the ambient air.
- ➤ **Noise pollution**: Monitoring average equivalent sound level over 24 hour period (Leq24), Day-night average sound level (Ldn) Percentile Level 90 (L90), and Maximum Level (Lmax)
- ➤ **Effluent quality**: Monitoring Temperature, pH, TDS ,SS, COD, Grease & oil and Flow Rate
- > **Safety:** Conducting emergency response exercise and providing preventive maintenance for emergency alarm system regularly.

Objectives and Project Information

Objectives

> To support an increasing demand for electricity and steam in Thaioil Group

Project Information:

- ➤ The small power plant is a co-generation plant using natural gas as fuel source
- Increasing Electricity production Capacity From 246.4 MW to 386.4 MW and Steam from 538.0 T/hr to 832.2 T/hr

Project Schedule:

- Construction Phase → June 2021 April 2023
- ➤ Operation Phase → May 2023

Construction Phase:

- Spraying water in the construction area to reduce the amount of particulate matter generated
- Having a cover sheet over trucks to prevent the fall-out of materials or equipment during transportation
- Limiting and controlling the speed of trucks entering construction area
- Establishing safety rules and/or procedures for contractors, and enforcing contractors to be strictly responsible for those rules and/or procedures
- Providing preventive maintenance for machines and equipment, and training contractors on how to operate them

Project Status: In a progress of applying construction permit

Contact Information

Government Relations Section, Thai Oil Public Company Limited
Tel: 0-2797-2999 Fax: 0-2797-2974